

**XX006657 RELOCATE EXISTING VIDEO DETECTION SYSTEM (COMPLETE INTERSECTION) (LCDOT)**

Effective: October 1, 2016

Revised:

LC801.07

**Description:** This work shall consist of the removal, storage, and relocation of an existing video detection system (complete intersection) from one traffic signal installation to another traffic signal installation.

**General:** The remote-controlled video system shall be removed and relocated as shown on the plans and/or as directed by the Traffic Engineer. Any damage sustained by the video detection system during the removal, storage, transport, and/or reinstallation operations shall be repaired or replaced in kind to the satisfaction of the Traffic Engineer at the Contractor's expense.

All holes drilled into signal poles, mast arms, or posts shall require rubber grommets to prevent the chafing of wires.

**Basis of Payment:** This item will be paid for at the contract unit price per each for RELOCATE EXISTING VIDEO DETECTION SYSTEM (COMPLETE INTERSECTION). *The unit price shall include all equipment, materials and labor required to disconnect the existing video detection system; package and store it; transport it; install the complete system in the new location; and in operation to the satisfaction of the Traffic Engineer.*