

SECTION 501 REMOVAL OF EXISTING STRUCTURES (LCDOT)

For use on LCDOT & IDOT let project with existing structure (section 501) removal items. Coordinate with Maintenance prior to the letting to have them check the structures scheduled for removal to determine if they want any of the components, parts other structure items. Delete this note from the Contract Specifications.

Effective: October 17, 2016

Revised: April 11, 2017

Description: This work shall consist of the removal of existing traffic and drainage structures or portions thereof.

General: The work shall be performed according to Section 501 of the “Standard Specifications” and the following:

All structures scheduled for removal will be examined by the Engineer, in coordination with LCDOT Maintenance, to determine if the item is suitable for salvage.

If maintenance wants any of the structure components, parts other structure items list them in the General Notes (3d) and include the following section. Delete this note from the Contract Specifications.

The structure items/components designated for salvage are listed on the plans under General Note 3d.

Items designated for salvage shall be carefully removed and stored at the location and in the manner designated by Engineer. Any of the material having salvage value which is damaged by the Contractor shall be replaced by the Contractor, at his/her own expense, with new items of the same kind and size. The cost of storing salvaged items shall be included in the unit cost of the guardrail being removed.

Items not designated for salvage shall be transported from the project site and dispose of them outside the ROW according to Article 202.03 of the “Standard Specifications”.

If maintenance doesn't want any of the structure components, parts other structure items then include following. Delete this note from the Contract Specifications.

None of the structure items/components scheduled for removal have been designated for salvage by LCDOT. The Contractor shall transport the removed culvert components from the project site and dispose of them outside the ROW according to Article 202.03 of the “Standard Specifications”.

Basis of Payment: This work will be paid for according to Article 501.07 of the “Standard Specifications”.