

SECTION 550 STORM SEWER (LCDOT) For use on LCDOT & IDOT let projects with proposed storm sewer. Delete this note from the Contract Specifications.

Effective: October 17, 2016

Description: This work shall consist of constructing storm sewers.

General: The work shall be performed according to Section 550 of the “Standard Specifications” and the following:

The cost of connecting proposed storm sewer to existing structures shall be included in the unit cost of the proposed storm sewer. Additional pipe required to complete the connections will be paid for at the contract unit price for STORM SEWER of the type, size and class required.

Temporary sheeting or bracing for sewer trenches that may be required shall be the responsibility of the Contractor. The cost of this work shall be included in the unit price for STORM SEWER of the type, size and class specified. Note if the project includes Utility trench work a similar spec should be included. Delete this note from the Contract Specifications.

At locations where the proposed storm sewer crosses over utilities, a 4" Styrofoam cushion shall be placed under the storm sewer when directed to do so by the Engineer. This work shall be included in the unit price for STORM SEWER of the type, size and class specified.

Basis of Payment: This work will be paid for according to Article 550.10 of the “Standard Specifications”.