

SECTION 551 STORM SEWER REMOVAL AND INSTALLATION (LCDOT)

For use on LCDOT & IDOT let project with storm sewer removal items. Coordinate with Maintenance prior to the letting to have them check the storm sewer scheduled for removal to determine if they want any of the pipes, end sections, or grates. Delete this note from the Contract Specifications.

Effective: October 17, 2016

Revised: April 11, 2017

Description: This work shall consist of the removal and/or installation of storm sewers, including laterals.

General: The work shall be performed according to Section 551 of the “Standard Specifications” and the following:

All storm sewer scheduled for removal will be examined by the Engineer, in coordination with LCDOT Maintenance, to determine if the item is suitable for salvage.

If maintenance wants any of the pipes, end sections or grates list them in the General Notes (3d) and include the following section. Delete this note from the Contract Specifications.

The storm sewer items/components designated for salvage are listed on the plans under General Note 3d.

Items designated for salvage shall be carefully removed and stored at the location and in the manner designated by Engineer. Any of the material having salvage value which is damaged by the Contractor shall be replaced by the Contractor, at his/her own expense, with new items of the same kind and size. The cost of storing salvaged items shall be included in the unit cost of the storm sewer being removed.

Items not designated for salvage shall be transported from the project site and dispose of them outside the ROW according to Article 202.03 of the “Standard Specifications”.

Trenches resulting from the removal of pipe culverts shall be backfilled in accordance with the applicable requirements of Article 550.07 of the “Standard Specifications”.

If maintenance doesn't want any of the pipes, end sections or grates due to stock on hand or the desired sections are damaged then include following. Delete this note from the Contract Specifications.

None of the storm sewer scheduled for removal has been designated for salvage by LCDOT. The Contractor shall transport the removed storm sewer items/components from the project site and dispose of them outside the ROW according to Article 202.03 of the “Standard Specifications”.

Trenches resulting from the removal of pipe culverts shall be backfilled in accordance with the applicable requirements of Article 550.07 of the “Standard Specifications”.

Basis of Payment: This work will be paid for according to Article 551.06 of the "Standard Specifications".