

SECTION 632 GUARDRAIL AND CABLE ROAD GUARD REMOVAL (LCDOT)

For use on LCDOT & IDOT let project with guardrail removal items. Maintenance has decided that they want the end shoe and first rail if a terminal end section is being removed. Coordinate with Maintenance to have them check the guardrail scheduled for removal to determine if they want any other components. Delete this note from the Contract Specifications.

Effective: October 17, 2016

Revised: April 11, 2017

Description: This work shall consist of the removal and disposal of existing guardrail, including traffic barrier terminals, and cable road guard.

General: The work shall be performed according to Section 632 of the “Standard Specifications” and the following:

All guardrail, terminal end sections, and reflectors scheduled for removal will be examined by the Engineer, in coordination with LCDOT Maintenance, to determine if the item is suitable for salvage.

If maintenance wants any parts of the guardrail list them in the General Notes (3d) and include the following section. Delete this note from the Contract Specifications.

The guardrail components designated for salvage are listed on the plans under General Note 3d.

Items designated for salvage shall be carefully removed and stored at the location and in the manner designated by Engineer. Any of the material having salvage value which is damaged by the Contractor shall be replaced by the Contractor, at his/her own expense, with new items of the same kind and size. The cost of storing salvaged items shall be included in the unit cost of the guardrail being removed.

Items not designated for salvage shall be transported from the project site and dispose of them outside the ROW according to Article 202.03 of the “Standard Specifications”.

If maintenance doesn't want any of the guardrail components including the end shoe and first rail due to stock on hand or the desired sections are damaged, then include following. Delete this note from the Contract Specifications.

None of the guardrail scheduled for removal has been designated for salvage by LCDOT. The Contractor shall transport the removed guardrail components from the project site and dispose of them outside the ROW according to Article 202.03 of the “Standard Specifications”.

Basis of Payment: This work will be paid for according to Article 632.04 of the “Standard Specifications”.