

20101100 TREE TRUNK PROTECTION (LCDOT)

Effective: January 1, 2007

Revised: May 19, 2014

Description: This work shall consist of furnishing, installing and removing tree trunk protection for trees adjacent to the project site.

General: The work shall be performed according to Article 201.05 of the "Standard Specifications" and the following:

Prior to construction, the Contractor shall install a snow fence or other highly visible barrier around designated trees in a manner meeting the Engineer's approval. Visual barriers, such as single strand wire or plastic flagging, are not acceptable for this purpose. The barrier shall be maintained in the proper location and in good repair until the completion of construction. Removal and disposal of the barrier shall be the Contractor's responsibility.

Method of Measurement: Tree Trunk Protection will be measured for payment as each per tree according to Article 201.10(c) of the "Standard Specifications".

Basis of Payment: This work will be paid for at the contract unit price per each for TREE TRUNK PROTECTION.