

K0026610 TRANSPLANTED SALVAGED TREES (LCDOT)

Effective: August 3, 2011

Revised: May 19, 2014

Description: This work shall consist of transplanting trees identified on the plans and/or identified by the Engineer in the field to new locations on the project site.

General: The work shall be performed according to Section 253 of the “Standard Specifications” and the following:

The Engineer will determine the new locations of the transplanted trees in the field. The work shall include watering, fertilizing and other operations necessary to reasonably ensure the health of the trees. The work shall be done to the Engineer's satisfaction.

Method of Measurement: Trees to be transplanted will be measured in place, in the new location, as individual plants.

Basis of Payment: This work will be paid for at the contract unit price per each for TRANSPLANTED SALVAGED TREES. *The unit price shall include all equipment, labor and materials required to successfully transplant the designated trees.*