

LC7800XX TEMPORARY THERMOPLASTIC PAVEMENT MARKINGS (LCDOT)

For use on LCDOT let projects only - do not include in IDOT let projects. Delete this note from the Contract Specifications.

Effective: January 1, 2008

Revised: May 19, 2014

Description: This work shall consist of furnishing and applying thermoplastic pavement markings to be used for temporary traffic staging.

General: When directed by the Engineer, this work shall be used in place of temporary pavement markings. The work shall be performed according to Section 780 of the "Standard Specifications", and the following:

Placement of the markings shall be limited to hand-operated equipment only.

The material shall be limited to thermoplastic pavement markings. The markings shall be installed in accordance to Article 708.05 of the "Standard Specifications" except that the temperature and calendar date restrictions as indicated may be waived by the Engineer.

The performance and inspection specification included in Article 780.11 will also be waived.

Method of Measurement: Lines will be measured for payment in place in feet. Double yellow lines will be measured as two separate lines. Words and Symbols shall conform to the sizes and dimensions specified in the Illinois manual of Traffic Control Devices and IDOT Standard 780001, and will be measured based on the total areas indicated in Table 1, Section 780 of the "Standard Specifications", or as specified on the plans.

Basis of Payment: This work will be paid for at the contract unit price per foot of applied line width, as specified for TEMPORARY THERMOPLASTIC PAVEMENT MARKING – LINE of the line width specified and/or at the contract unit price per square foot for TEMPORARY THERMOPLASTIC PAVEMENT MARKING – LETTERS AND SYMBOLS. *The unit price shall include all equipment, materials and labor required to furnish and apply the temporary thermoplastic pavement markings.*