

LC600204 FENCE TO BE REMOVED AND REPLACED (LCDOT) For use on LCDOT let projects only - do not include in IDOT let projects. Delete this note from the Contract Specifications.

Effective: August 1, 2011

Revised: May 19, 2014

Description: This work shall consist of removing and disposing of an existing fence from the project site. The work shall also include furnishing and installing a new fence at a location shown on the plans and/or designated by the Engineer.

Materials: The new fence shall be of a style and material similar to the existing fence. The Engineer shall approve the proposed fence style and material prior to installation.

General: *The Contractor shall remove all components of the existing fence, including any concrete used to anchor fence posts, bracing, guy wires, posts, and/or gates. All removed materials shall be disposed of outside the limits of the right-of-way according to Article 202.03 of the "Standard Specifications" and/or as directed by the Engineer.*

Prior to constructing the new fence, the area along the line of the fence shall be cleared according to Section 201 of the "Standard Specifications". The new fence shall be installed at the proposed right-of-way line, easement line, and/or as directed by the Engineer.

Chain Link fences shall be constructed according to Section 664 of the "Standard Specifications".

Woven Wire fences shall be constructed according to Section 665 of the "Standard Specifications".

All other types of fences shall be erected according to the manufacturer's recommendations.

Method of Measurement: This work will be measured for payment in feet, along the top of the new installed fence, from center to center of end posts, excluding the length occupied by gates.

Basis of Payment: This work will be paid for at the contract unit price per foot for FENCE TO BE REMOVED AND REPLACED. *The unit price shall include all equipment, materials and labor required to remove and dispose of the existing fence and to furnish and erect the replacement fence.*