

## **XX000856 MAILBOX REMOVAL AND RELOCATION (LCDOT)**

Effective: September 1, 2011

Revised: May 19, 2014

**Description:** This work shall consist of removing and relocating an existing mail box.

**General:** This work shall consist of removing and relocating an existing mail box to the proposed location shown on the plans. The new location of the mail box shall be approved by the Engineer.

*The relocated mailbox shall be installed on a new 4" x 4" square or 4½" diameter round treated wood post. The new post shall be embedded no more than 24" into the ground. The resulting hole shall be backfilled with a suitable excavated material, approved by the Engineer.*

*The existing post shall be removed and disposed of according to the requirements of Article 202.03 of the "Standard Specifications". The hole for the existing post shall be backfilled and the area restored.*

**Method of Measurement:** This work will be measured for payment as each mailbox to be relocated.

**Basis of Payment:** This work will be paid for at the contract unit price per each for MAILBOX REMOVAL AND RELOCATION. *The unit price shall include all equipment, materials and labor required to relocate the mailbox and to restore the existing location. No additional compensation will be allowed for any temporary relocation or for the removal and disposal of the existing post.*