

X0326458 PAVEMENT REPLACEMENT, SPECIAL (LCDOT) For use on all LCDOT projects with resurfacing. Fill in the boxes below with the binder depth and N value. Delete this note from the Contract Specifications.

Effective: January 1, 2007

Revised: May 20, 2014

Description: This pay item is for hot-mix asphalt pavement removed for storm sewer, culvert, sanitary sewer, water main and/or other underground work requiring a trench. This work shall consist of removing existing pavement, excavating as necessary base and subbase materials, and replacing the pavement, to include subbase and base courses, with Hot-Mix Asphalt Binder Course, to the limits shown on the plans.

Materials: Aggregate subbase and base materials shall meet the requirements of Article 1004.04 of the "Standard Specifications".

The Hot-Mix Asphalt Binder Course will be designed and constructed according to Section 406 of the "Standard Specifications".

General: The work shall be performed according to the applicable portions of Section 440 [Pavement Removal] and Section 442 [Pavement Patching] of the "Standard Specifications" and the following:

The perimeter of the removal area shall be saw cut full depth, prior to removing the pavement.

The pavement replacement shall consist of " Hot-Mix Asphalt Binder Course IL-19.0, N70 which shall be placed in a minimum of 3 lifts.

Open cuts or patches temporarily filled with stones or partial base course shall not be left in aggregate (unpaved) overnight.

Method of Measurement: Pavement Replacement will be measured in place, and the area computed in square yards. *The maximum width shall be equal to the allowable trench width plus 12".*

Basis of Payment: This work will be paid for at the contract unit price per square yard for PAVEMENT REPLACEMENT. *The unit price shall include all equipment, labor and materials required to replace the pavement.*