

## **XX206400 MAILBOX POST (LCDOT)**

Effective: January 1, 2007

Revised: May 19, 2014

**Description:** This work shall consist of removing and replacing existing broken and/or rotted mailbox post(s) at locations shown on the plans and/or as directed by the Engineer.

**General:** The Engineer will determine which mailbox posts need to be replaced. This work shall consist of:

- Removing the existing mailbox from the broken and/or rotted post.
- Removing the existing post.
- Installing a new 4" x 4" square or 4½" diameter round treated wood post
- Mounting the existing mailbox on the new post.

The new post shall be embedded no more than 24" into the ground. The resulting hole shall be backfilled with suitable excavated material approved by the Engineer.

The old post shall be disposed of according to the requirements of Article 202.03 of the "Standard Specifications".

**Method of Measurement:** This work will be measured for payment as one each for each new mailbox post installed.

**Basis of Payment:** This work will be paid for at the contract unit price per each for MAILBOX POST. *The unit price shall include the removal and disposal of the existing post, backfilling the post hole(s) and all equipment, materials and labor required to install the new mailbox post. No additional compensation will be allowed for any temporary relocation of the mailbox.*