

Z0055905 TEMPORARY CONSTRUCTION FENCE (LCDOT)

Effective: June 21, 2011

Revised: May 19, 2014

Description: This work shall consist of furnishing, installing, maintaining, removing and disposing of temporary construction fence. The temporary construction fence shall be installed at locations shown on the plans and/or as designated by the Engineer.

General: The temporary construction fence shall be installed to clearly define the project work area. The fence shall be installed according to Article 201.05 (a) Temporary Fencing of the "Standard Specifications" and the following:

The fence shall be a plastic mesh fence colored orange.

The fence shall be erected prior to beginning construction operations and shall be maintained throughout the duration of the construction project or until the Engineer determines that the fence is no longer needed. Upon completion of the project the fence shall be removed and any damage caused by the fence installation and/or removal shall be repaired. The cost of repairs shall be included in the unit cost of the temporary fence.

Method of Measurement: This work will be measured for payment in place in feet of temporary construction fence installed.

Basis of Payment: This work will be paid for at the contract unit price per foot for TEMPORARY CONSTRUCTION FENCE. *The unit price shall include all materials, labor and equipment necessary to properly install the fence, maintain it and to remove and dispose of the used materials at the completion of the project.*