

**Z0062456 TEMPORARY PAVEMENT (LCDOT)** For use on LCDOT let projects only  
- do not include in IDOT let projects. For IDOT let projects use the D1 spec TEMP  
PVMT. Delete this note from the Contract Specifications.

Effective: January 1, 2007

Revised: May 19, 2014

**Description:** This work shall consist of constructing, maintaining, and removing temporary pavement at the locations shown on the plans and/or as directed by the Engineer.

**Materials:** The hot-mix asphalt materials shall meet the requirements of Section 1030 of the "Standard Specifications".

**General:** The work shall be performed according to Section 355 of the "Standard Specifications" and the following:

*The temporary pavement shall consist of 8" of Hot-Mix Asphalt Base Course constructed and compacted according to Section 355 of the "Standard Specifications". The temporary pavement shall be placed and compacted in a minimum of two lifts on a prepared subgrade.*

*The Hot-Mix Asphalt mixture shall be as shown on the plans.*

*Article 355.08 of the "Standard Specifications", shall not apply.*

*The temporary pavement shall be removed according to Section 440 of the "Standard Specifications". The removed pavement shall be disposed of outside the right-of-way according to Article 202.03 of the "Standard Specifications".*

**Method of Measurement:** Temporary Pavement will be measured for payment in place, and the area computed in square yards.

**Basis of Payment:** This work will be paid for at the contract unit price per square yard for TEMPORARY PAVEMENT. *The unit price shall include all equipment, materials and labor required to furnish, place, maintain and remove the temporary pavement.*