

NORTH BRANCH CHICAGO RIVER WATERSHED-BASED PLAN



05/22/08

FOR LAKE AND COOK COUNTIES, ILLINOIS



STORMWATER
MANAGEMENT
COMMISSION
333-B PETERSON
ROAD
LIBERTYVILLE,
ILLINOIS 60048

This publication was prepared using U.S. Environmental Protection Agency funding under Section 319 of the Clean Water Act distributed by the Illinois Environmental Protection Agency. The findings and recommendations contained herein are not necessary those of the funding agency.

TABLE OF CONTENTS

EXECUTIVE SUMMARY	I
INTRODUCTION.....	I
How the North Branch Chicago River Project Began	ii
The North Branch Chicago River Watershed-Based Plan	ii
USEPA Watershed-Based Plan Upgrades.....	iii
Using this Document.....	v
Watershed, River, Project & Plan.....	v
Plan, Goals & Objectives.....	v
Watershed Resource Inventory & Assessment.....	v
Watershed Restoration and Management Techniques	v
Action Plan	v
From Plan to Performance.....	vi
CHAPTER 1 : WATERSHED, RIVER, PROJECT & PLAN	1-1
1.1 North Branch Chicago.....The Watershed	1-1
1.1.1 What is a Watershed?.....	1-1
1.1.2 North Branch Chicago River Watershed	1-2
1.2 North Branch Chicago.....River or Ditch?	1-7
1.3 The North Branch Partnership	1-7
1.4 The North Branch Watershed Plan.....	1-8
1.4.1 Setting Goals & Objectives for the Plan.....	1-8
1.4.2 Assessing the Watershed Condition.....	1-9
1.4.3 Compiling a “toolbox” of watershed best management practices.....	1-9
1.4.4 Developing an Action Plan for the North Branch	1-9
1.5 Into the FutureA Vision for the North Branch	1-10
CHAPTER 2 : PLAN GOALS & OBJECTIVES	2-1
2.1 Developing Plan Goals and Objectives	2-1
2.2 North Branch Chicago River Watershed Project Mission Statement.....	2-4
2.3 North Branch Chicago River Watershed Building Blocks Worksheet.....	2-4
CHAPTER 3 : WATERSHED RESOURCE INVENTORY & ASSESSMENT	3-1
3.1 Assessment Methodology.....	3-1
3.1.1 Data Collection Strategies.....	3-1
3.1.2 Geographic Information Systems.....	3-3
3.2 Watershed Setting.....	3-4
3.2.1 Geologic Setting	3-4
3.2.2 Pre-European Settlement Vegetation.....	3-4
3.2.3 Climate.....	3-7
3.2.4 Soils.....	3-7
3.2.4.1 Hydrologic Soil Groups	3-8
3.2.4.2 Hydric Soils	3-10
3.3 Historic Settlement and Resources.....	3-12
3.3.1 Human Settlement	3-12
3.3.2 Archeological Sites.....	3-13

3.3.3	Historic Structures.....	3-13
3.4	Jurisdictions in the North Branch Chicago River Watershed	3-15
3.5	Demographics.....	3-20
3.5.1	Lake County Demographic Forecast.....	3-20
3.5.1.1	Population & Households.....	3-21
3.5.1.2	Employment	3-22
3.5.2	Cook County Demographic Forecast	3-29
3.5.2.1	Population & Households	3-31
3.5.2.2	Employment	3-31
3.6	North Branch Chicago River Watershed Land Use	3-32
3.6.1	Land Use in Lake County	3-32
3.6.1.1	West Fork Land Use in Lake County.....	3-33
3.6.1.2	Middle Fork Land Use in Lake County.....	3-33
3.6.1.3	Skokie River Land Use in Lake County	3-33
3.6.2	Land Use in Cook County	3-34
3.6.3	Impacts of Land Use on Flooding, Water Quality and Streams	3-37
3.6.4	Open Land in the North Branch Chicago River Watershed.....	3-42
3.6.5	Transportation System.....	3-59
3.7	Conservation Land.....	3-61
3.7.1	Conservation Land in Lake County.....	3-61
3.7.2	Lands Identified for Conservation in Lake County	3-64
3.7.3	Conservation Land in Cook County	3-65
3.7.4	Greenways and Trails.....	3-67
3.8	Plants & Animals: Threatened & Endangered Species and Natural Areas.....	3-71
3.8.1	Threatened & Endangered Species.....	3-71
3.8.1.1	Sites of Threatened and Endangered Species	3-71
3.8.1.2	T&E Species Protection	3-71
3.8.2	Natural Areas & Nature Preserves.....	3-74
3.8.3	Development Impacts on T&E Species and Natural Areas	3-80
3.8.4	Planning Considerations for T&E Species and Natural Areas	3-80
3.9	Wetlands.....	3-80
3.9.1	Lake County Wetlands.....	3-81
3.9.1.1	High Quality (ADID) Wetlands.....	3-83
3.9.2	Cook County Wetlands	3-83
3.9.3	Future Wetland Impacts.....	3-84
3.10	Cultural Resources	3-85
3.11	Lakes	3-86
3.12	The River.....	3-88
3.12.1	General Description.....	3-88
3.12.1.1	West Fork	3-90
3.12.1.2	Middle Fork	3-90
3.12.1.3	Skokie River	3-90
3.12.2	River Assessment: A Stream Inventory, Lake County.....	3-91
3.12.2.1	Channel Conditions – Lake County	3-93
3.12.2.2	Discharge Points.....	3-102
3.12.2.3	Riparian Corridor/Floodplain.....	3-103
3.12.2.4	Aquatic Habitat.....	3-104

3.12.2.5	Aquatic and Terrestrial Organisms.....	3-106
3.13	Water Quality.....	3-107
3.13.1	North Branch Chicago River Urbanization and Water Quality	3-108
3.13.2	Assessment Data	3-109
3.13.2.1	IEPA Water Quality Reports	3-110
3.13.2.2	Biological Monitoring.....	3-113
3.13.2.3	Chemical Monitoring Data	3-115
3.13.2.4	Metal Contamination in North Branch Chicago River Sediments.....	3-120
3.13.3	Point Sources of Pollution.....	3-121
3.13.3.1	NPDES Permits.....	3-121
3.13.3.2	Sanitary and Stormsewer Infiltration and Inflows (I&I)	3-124
3.13.3.3	Other Potential Pollution Sources in the North Branch Chicago River.....	3-125
3.13.3.4	Conclusions.....	3-126
3.13.4	Nonpoint Source Pollutant Loading Analysis	3-129
3.13.4.1	North Branch Chicago River Watershed Pollutant Load Estimates	3-129
3.13.5	Water Quality Summary	3-133
3.13.6	An estimate of load reduction expected from management measures.....	3-134
3.14	Flooding.....	3-142
3.14.1	Hydrology and Hydraulics	3-142
3.14.1.1	North Branch: A Flashy Hydrology	3-142
3.14.1.2	Existing Studies/Floodplain Mapping	3-147
3.14.1.3	Drainage patterns: Defining stormsewersheds.....	3-150
3.14.1.4	Hydraulic Impoundments	3-152
3.14.1.5	Regulating Runoff/Preserving Floodplains, Lake County.....	3-153
3.14.1.6	Conclusions.....	3-156
3.14.2	Flood Damage	3-159
3.14.2.1	Studies/Reports.....	3-159
3.14.2.2	Flood Control Projects	3-161
3.14.2.3	Skokie Headwaters and North Chicago Flood Damage Reduction Feasibility Study (2006).....	3-164
3.14.2.4	Lake County SMC Flood Problem Areas Inventory.....	3-167
3.14.2.5	Preliminary Identification of Structures at Flood Risk	3-170

CHAPTER 4 : WATERSHED RESTORATION AND MANAGEMENT TECHNIQUES4-1

4.1	Water Quality Measures	4-1
4.1.1	Preventative Measures: Protecting Water Quality.....	4-1
4.1.1.1	Regulatory Requirements	4-2
4.1.1.2	Water Quality Best Management Practices	4-4
4.1.1.3	Riparian Buffers.....	4-7
4.1.1.4	Stream Maintenance	4-7
4.1.1.5	Nonpoint Source Pollution Prevention Program	4-8
4.1.2	Remedial Measures: Improving Water Quality	4-9
4.1.2.1	Detention Basin Retrofits.....	4-9
4.1.2.1.1	North Branch Detention Basin Inventory, Lake County	4-10
4.1.2.2	Outfall Retrofits Created Wetland Meanders	4-14
4.1.2.3	Streambank Stabilization.....	4-14
4.1.2.4	Correcting Sanitary and Stormsewer Infiltration and Illicit Discharges.....	4-15

4.2	Flood Damage Reduction Measures	4-16
4.2.1	Preventative Measures: Keep Flood Damage from Expanding	4-16
4.2.1.1	Floodplain Zoning.....	4-16
4.2.1.2	Floodplain Regulations	4-16
4.2.1.3	Floodplain Acquisition.....	4-17
4.2.1.4	Runoff Reduction.....	4-17
4.2.1.4.1	Infiltration Techniques.....	4-17
4.2.1.4.2	Alternative Site Designs	4-18
4.2.1.4.3	Stormwater Regulations.....	4-21
4.2.2	Remedial Measures: Fixing Flood Damage	4-22
4.2.2.1	Structural Flood Control.....	4-22
4.2.2.1.1	Reservoirs/Regional Detention.....	4-23
4.2.2.1.2	Detention Basins	4-23
4.2.2.1.3	Levees and Floodwalls.....	4-24
4.2.2.1.4	Barriers	4-24
4.2.2.1.5	Improved Channel Conveyance	4-24
4.2.2.1.6	Drainage Improvements.....	4-25
4.2.2.2	Non-Structural Flood Control	4-25
4.2.2.2.1	Building Relocation	4-25
4.2.2.2.2	Buyouts/Acquisition.....	4-26
4.2.2.2.3	Building Elevation.....	4-26
4.2.2.2.4	Floodproofing	4-26
4.2.2.2.5	Runoff Reduction	4-27
4.2.2.2.6	Insurance	4-27
4.3	Natural Resource Measures	4-28
4.3.1	Preventative Measures: Natural Resources Protection.....	4-28
4.3.1.1	Protecting Open Space and Natural Areas	4-28
4.3.1.1.1	Protected Ownership.....	4-28
4.3.1.1.2	Conservation Design Developments.....	4-31
4.3.1.2	Threatened and Endangered (T&E) Species	4-32
4.3.1.3	Greenways and Trails	4-32
4.3.1.4	Wetlands.....	4-33
4.3.1.4.1	No-Net-Loss/Wetland Mitigation.....	4-34
4.3.1.4.2	Management Plans for ADID Wetlands.....	4-34
4.3.1.4.3	Acquisition of High Priority Wetlands.....	4-35
4.3.1.4.4	Wetland/Stream Buffers.....	4-35
4.3.1.4.5	Wetland Incentives and Cost-Share Opportunities	4-35
4.3.2	Remedial Measures: Restoring Natural Resources	4-37
4.3.2.1	Stream Restoration.....	4-37
4.3.2.1.1	Pool/Riffle Complexes.....	4-37
4.3.2.1.2	Dam Removal	4-37
4.3.2.2	Wetland Enhancement and Restoration	4-38
4.4	Watershed Coordination Measures	4-38
4.4.1	Planning and Policy Coordination.....	4-38
4.4.1.1	Lake County North Branch Watershed Management Board	4-38
4.4.1.2	North Branch Planning Committee	4-38
4.4.1.3	MWRD Watershed Planning Council.....	4-39

4.4.2 Regulatory Coordination	4-39
4.4.2.1 The Watershed Development Ordinance.....	4-39
4.4.2.2 Wetlands Regulations.....	4-39
4.4.2.3 Municipal Advisory Committee	4-40
CHAPTER 5 : ACTION PLAN	5-1
5.1 Watershed Roles & Responsibilities.....	5-2
5.2 Programmatic Action Plan.....	5-11
5.2.1 Goal 1: Improve Water Quality in the North Branch Chicago River	5-11
5.2.2 Goal 2: Reduce Flood Damages in the North Branch Chicago River	5-13
5.2.3 Goal 3: Protect and Enhance Natural Resources and Provide Associated Recreational Opportunities	5-18
5.2.4 Goal 4: Develop a Public Information and Education Program within the Watershed Communities.....	5-21
5.2.5 Goal 5: Improve Participation and Coordination in Watershed Improvement Activities	5-24
5.3 An Estimate of Load Reduction Expected From Management Measures.....	5-25
5.4 Site Specific Action Plan	5-28
CHAPTER 6 : FROM PLAN TO PERFORMANCE	6-1
6.1 Getting Projects Done.....	6-1
6.1.1 Coordination and Cooperation	6-1
6.1.2 Funding.....	6-2
6.2 Evaluating Plan Performance.....	6-2
6.3 Updating the Plan	6-2

LIST OF APPENDICES

APPENDIX LETTER	TITLE	PAGE NUMBER
A	Meeting Summaries	A1
B	Summary of North Branch Stream Reach Characteristics	B1 – B14
C	Discharge Points into the North Branch	C1 –C35
D	Hydraulic Structures in the North Branch	D1 – D9
E	Stream Inventory Photo Log	E1 – E46
F	Calculating Non-Point Source Pollutant Loading and Pollutant Loading Maps for North Branch Subwatersheds in Lake & Cook Counties	F1 – F39
G	Detention Basin Inventory Summary Table	G1 – G31
H	Potential Regionally Significant Storage Locations	H1 – H5
I	Existing Studies, Reports, Mapping and Data	I1 – I14
J	Funding Sources for Watershed Projects	J1 – J15
K	Maintenance, Management and Monitoring Plans for Recommended BMPs in the North Branch Watershed	K1 – K15
L	Glossary	L1 – L10
M	Acronyms and Abbreviations	M1 – M5
N	Education Plans	N1 – N13
O	Water Quality Monitoring Program for Metals	O1 – O3

LIST OF FIGURES

FIGURE NUMBER	TITLE	PAGE NUMBER
	CHAPTER 1	
1-1	Watershed Management Units	1-1
1-2	Regional Location of North Branch Watershed	1-3
1-3	North Branch Watershed Map	1-4
1-4	North Branch Chicago River Watershed in Lake and Cook Counties	1-5
	CHAPTER 3	
3-1	Glacial Moraines in Northeastern Illinois	3-5
3-2	Pre-Settlement Vegetation within Lake and Cook Counties	3-6
3-3	Hydrologic Soil Groups Lake and Cook Counties	3-9
3-4	Hydric Soils in Lake and Cook Counties	3-11
3-5	Drainage Districts - Lake County	3-17
3-6	Municipalities and Townships – Lake and Cook Counties	3-18
3-7	County Board Districts and Congressional Districts - Lake County	3-19
3-8	2000 To 2030 Population Change – Lake and Cook Counties	3-23
3-9	2000 To 2030 Employment Change – Lake and Cook Counties	3-24
3-10	2000 Population Density – Lake and Cook Counties	3-25
3-11	2030 Population Density – Lake and Cook Counties	3-26
3-12	2000 Employment Density – Lake and Cook Counties	3-27
3-13	2030 Employment Density – Lake and Cook Counties	3-28
3-14	2001 Land Use - Lake and Cook Counties	3-35
3-15	Parcels of Unknown Ownership	3-45
3-16	Open Space Inventory	3-47
3-17	Owner Type of Open Parcels	3-50
3-18	Public/Private Ownership	3-52

3-19	Protection Status	3-56
3-20	Recreational Use Type	3-58
3-21	2006-2011 Transportation Improvement Plan	3-60
3-22	Natural Areas, Illinois Nature Preserves and Threatened and Endangered Species	3-63
3-23	Forest Preserve District Land Holdings within the Cook County Study Area	3-66
3-24	Existing Greenways and Trails System with Protected Open Space-Lake County	3-69
3-25	Existing and Proposed Greenways and Trails	3-70
3-26	Natural Areas and Illinois Nature Preserves in Lake and Cook Counties	3-75
3-27	Biodiverse Areas – Lake and Cook Counties	3-77
3-28	Fieldwork Locations in Lake County Study Area	3-78
3-29	Remnant Landscapes	3-79
3-30	Wetland Inventory Map – Lake and Cook Counties	3-82
3-31	Surface Water Resources - Lake County	3-87
3-32	North Branch Chicago River Watershed	3-89
3-33	Stream Inventory Stream Reaches – Lake County	3-92
3-34	Pool/Riffle Development within Lake County	3-97
3-35	Streambank Erosion within Lake County	3-98
3-36	Sedimentation within Lake County	3-99
3-37	Instream Debris Loads within Lake County	3-100
3-38	Biotic Integrity Compared to Urbanization	3-109
3-39	Category 5 Impaired Waters	3-111
3-40	NPDES Permit Sites	3-123
3-41	Landfill and Compost Sites	3-127
3-42	US EPA Superfund Sites	3-128
3-43	Top Ranked Pollutant Loading Rates by Stormsewershed – Cook and Lake County	3-132
3-44	Rain and Stream Gages	3-144
3-45	Rainfall Hydrograph at Dundee Road (August 1990)	3-145
3-46	Comparative Hydrographs	3-146
3-47	Floodplains - Lake and Cook Counties	3-149
3-48	Stormsewersheds - Lake and Cook Counties	3-151
3-49	Gaged Discharges vs. Tributary Area	3-158
3-50	Flood Control Project Locations- Lake County	3-165
3-51	Potential Flood Problem Areas within the Skokie River Watershed- Lake County	3-166
3-52	Flood Problem Areas - Lake County	3-168
3-53	Flood of Record Boundaries - Lake County	3-175
	CHAPTER 5	
5-1	Open Space Within the Floodplain – Lake County	5-16
5-2	Potential Regional Storage – Lake County	5-17
5-3	Detention Basins Recommended for Water Quality Retrofits – Lake County	5-29
5-4	Priority Stream Inventory Reaches – Lake County	5-31
5-5	Potential Wetland Restoration Sites – Lake County	5-32
5-6	Priority Wetland Restoration Sites – Lake County	5-33
5-7	Potential Open Space Protection Sites – Lake County	5-34
5-8	Priority Open Space Protection Sites – Lake County	5-35

	APPENDIX F	
F-1	Pollutant Loading Biochemical Oxygen Demand	F-28
F-2	Pollutant Loading Chemical Oxygen Demand	F-29
F-3	Pollutant Loading Total Suspended Solids	F-30
F-4	Pollutant Loading Total Dissolved Solids	F-31
F-5	Pollutant Loading Total Nitrogen	F-32
F-6	Pollutant Loading Total Phosphorus	F-33
F-7	Pollutant Loading Total Copper	F-34
F-8	Pollutant Loading Total Lead	F-35
F-9	Pollutant Loading Total Zinc	F-36
F-10	Pollutant Loading Total Cadmium	F-37

LIST OF TABLES

TABLE NUMBER	TITLE	PAGE NUMBER
	CHAPTER 1	
1-1	A Quick View of the North Branch	1-2
1-2	Topics Covered in Watershed Assessment	1-9
	CHAPTER 2	
2-1	Key Problems and Opportunities in the North Branch Chicago River Watershed	2-11
	CHAPTER 3	
3-1	Watershed Assessment Data Sources	3-2
3-2	GIS Layers Used for the Watershed Assessment	3-3
3-3	Predominant Soil Types , North Branch Watershed, Lake and Cook Counties	3-8
3-4	Characteristics of Hydrologic Soil Groups	3-8
3-5	Acreage of Hydrologic Soil Groups in the Watershed, Lake and Cook Counties	3-10
3-6	Acreage of Hydric Soils in the Watershed, Lake and Cook Counties	3-10
3-7	Historic Bridges	3-14
3-8	Major Political Jurisdictions in the North Branch Chicago River Watershed	3-16
3-9	CMAQ Forecast Data for the North Branch Chicago River Watershed, Lake County	3-20
3-10	CMAQ Forecast Data for the North Branch Chicago River by Subwatershed, Lake County	3-21
3-11	CMAQ Forecast Data for the North Branch Watershed, Cook County	3-29
3-12	CMAQ Forecast Data for the North Branch by Subwatershed, Cook County	3-30
3-13	Land Use in the North Branch Watershed	3-36
3-14	Impervious Cover Estimates North Branch Chicago River Watershed	3-37
3-15	Watershed Development Trends, Lake County	3-38
3-16	Geometric Mean Concentrations of Pollutants in Stormwater Runoff from Selected Urban Source Areas	3-40
3-17	Highway Runoff Constituents and their Primary Sources	3-41
3-18	Acreage of Open Space in North Branch Watershed	3-43
3-19	Parcel Size and Estimated Value	3-44
3-20	Owner Type Summary for Open Parcels	3-48
3-21	Owner Type Summary for Partially Open Parcels	3-49
3-22	Public/Private Ownership	3-51
3-23	Protection Status by County and Watershed	3-54
3-24	Protection Status by Subwatershed	3-55
3-25	Forest Preserves in the North Branch Watershed - Lake County	3-61
3-26	Definitions: State and Federal T&E Species	3-71
3-27	T&E Plant and Animal Species in the North Branch Chicago River Watershed	3-73
3-28	Wetlands in the North Branch Watershed	3-81
3-29	Protection for ADID Wetlands	3-83
3-30	North Branch Lakes, Lake Co.	3-86

3-31	Lake County Stream Reaches	3-91
3-32	Channel Shape Characteristics, Lake County	3-94
3-33	Pool/Riffle Development in Lake County Reaches	3-94
3-34	Lake County Streambank Erosion Problems	3-95
3-35	Sediment Accumulation in Lake County	3-96
3-36	Instream and Overbank Debris Load in Lake County Reaches	3-101
3-37	Hydraulic Structures North Branch, Lake County	3-101
3-38	Discharge Points for North Branch Chicago River, Lake County	3-103
3-39	Land Use in Riparian Corridor, Lake County	3-103
3-40	Vegetation on Stream Banks, Lake County	3-104
3-41	Predominant Substrate Composition, Lake County	3-104
3-42	Number of Stream Reaches with Instream Fish Cover	3-106
3-43	Examples of Point and Nonpoint Source Pollution	3-107
3-44	Summary of Use Support Assessment Criteria and Biological Characteristics for Illinois Streams	3-110
3-45	IEPA Two-Year Schedule for TMDL Development	3-112
3-46	IDNR Lake Michigan Tributaries Fish Survey, July 27-31, 2006	3-114
3-47	MWRD Study of Benthic Macroinvertebrate Communities, 2006	3-115
3-48	IEPA Middle Fork Chemical Water Quality Data at Station HCCC-02	3-116
3-49	IEPA North Branch Chicago River Average Water Contamination Analysis From April 1999 through December 2003	3-117 – 3-120
3-50	IEPA North Branch Chicago River Sediment Contamination Analysis	3-121
3-51	NPDES Permitted Discharges to the North Branch Chicago River	3-122
3-52	Landfill Locations in the North Branch Chicago River Watershed	3-125
3-53	Pollutants Addressed in Loading Analysis	3-126
3-54	Average Pollutant Loading Rates by SSS for Priority Pollutants in the North Branch Chicago River Watershed (pounds/acre/year)	3-130
3-55	Estimated Annual Pollutant Loading Rates by Stormsewershed	3-131
3-56	Pollutant Load Reduction – Detention Basin Retrofits	3-136
3-57	Pollutant Load Reduction – Outfall Retrofits/Repairs	3-137
3-58	Pollutant Load Reduction – Stream Restoration and Maintenance	3-138
3-59	Pollutant Load Reduction – Potential Wetland Restoration Sites	3-138
3-60	Pollutant Load Reduction – Open Space Protection	3-139
3-61	Pollutant Load Reduction – Flood Mitigation Sites	3-140
3-62	Pollutant Load Reduction – Hydraulic Structures	3-141
3-63	Estimated Annual Pollutant Load Reduction for Streambank Stabilization by Stream Reach	3-142
3-64	Stream Gage Stations in the North Branch Watershed	3-144
3-65	Hydraulic Analysis and Floodplain Mapping Limits for Lake County	3-149
3-66	Stormsewersheds (SSS)	3-151
3-67	North Branch Flows per Tributary Area (FIS Study)	3-155 – 3-157
3-68	SCS Annual Projected Flood Damage in the North Branch by the Year 2000	3-160
3-69	Projected Residential Damage by Subwatershed for the North Branch, Lake & Cook Counties	3-161
3-70	USACE Annual Projected Flood Damage through 2020	3-162
3-71	Proposed/Constructed Flood Control Reservoirs North Branch Watershed	3-163
3-72	Flood Problem Sites North Branch Chicago River Watershed	3-170
3-73	Flood Damage Profile for the North Branch Watershed Flood Problem Areas Inventory, 1995	3-171

3-74	Preliminary Identification of Structures Located within the 100-Year Floodplain of the North Branch Chicago River, Lake & Cook Counties	3-173 – 3-174
	CHAPTER 4	
4-1	BMP Effectiveness Toward Meeting BMP Objective	4-5
4-2	Comparison of Median Pollutant Removal Efficiencies	4-6
4-3	Median Pollutant Removal Reported for Selected BMP Groups: Fecal Coliform, Hydrocarbons and Selected Trace Metals	4-6
4-4	Potential Pollutant Removal Capability of Urban Stream Buffers	4-7
4-5	Source Reduction Activities	4-9
4-6	North Branch Chicago River Watershed Detention Basins	4-11
4-7	North Branch Chicago River Watershed Detention Basin Types & Pollutant Removal Effectiveness	4-20
4-8	Relationship Between Impervious Cover and Stream Quality	4-20
4-9	Innovative Site Planning Techniques and Their Effect on Impervious Cover	4-22
4-10	WDO Runoff Volume Reduction Hierarchy	4-22
4-11	Benefits and Drawbacks to Structural Flood Control Measures	4-23
	CHAPTER 5	
5-1	North Branch Chicago River Watershed Partners, Lake County	5-2
-	Programmatic Action Plan	-
-	Site Specific Action Plan - Organized by Community	-