

SEDIMENT CONTROL FOR SITE DESIGN



Treatment Trains & Phased Plans

Session Objectives

- A treatment train is a **sequence** of sediment controls
- SESC design is an **iterative** process
- **Visit** the project site!


Distance	Elev Gain	Time
1.31 mi	14 ft	28m 26s



Treatment Trains

- “Treatment” implies the removal of stormwater volume or pollution that has already been generated
- SESC (Sediment Control portion of SESC)
- Utilizes 2 or more processes to maximize control of pollutants from site runoff
- Different processes achieve different goals... commonly:
 - Minimizing runoff rate
 - Removing / filtering suspended solids and other pollutants

An Iterative Process



Detention basin + temporary riser +
compensatory storage basin + double row
silt fence + rip rap apron + ditch checks =
no sediment leaving the site



Phased SESC Plans

- **Timing** is key
 - Include BMPs as part of demolition / existing conditions plan
 - Phasing will impact the EOPC
 - Discuss expectations at pre-con meeting
 - Proper installation & maintenance of BMPs
 - Construct stormwater management systems first
- Dewatering, Cofferdams, Silt Curtains





Case Study Glenview Park Golf Club

- The Big Picture
- Watershed Review




Case Study


GPGC

2010 Village Stormwater Task Force

2008 Flooding Event




Existing Watershed



Case Study GPGC



Master Plan



Case Study GPGC

Legend

 **Detention Ponds**

 **Ridge Line**

North Outfall



EROSION CONTROL / SITE CONSTRUCTION SEQUENCE PLAN

WORK AREA 1 (COMPLETE SITE) - INITIAL EROSION CONTROL IMPROVEMENTS

- 1) INSTALL PERIMETER SILT FENCE AROUND ENTIRE GOLF COURSE SITE AS SHOWN ON EROSION CONTROL PLAN (SHEET C03).
- 2) INSTALL CONSTRUCTION ENTRANCE AT SHERMAN ROAD ENTRANCE AND WANT ACCESS.
- 3) INSTALL ADDITIONAL EROSION CONTROL MEASURES (CONCRETE WASHOUT, FILTER BARRIERS, & DOOR LOGS AROUND ALL EXISTING DRAINAGE STRUCTURES ON SITE.
- 4) INSTALL SILT FENCE AROUND ALL EXISTING DETENTION BASINS AT DESIGN HIGH WATER LEVEL LINE.
- 5) INSTALL SEDIMENT CONTROL STRUCTURE (SEDIMENT TRAP) AT NORTHWEST CORNER OF SITE TO SERVE AS SOUTH AREA EROSION CONTROL MANAGEMENT STRUCTURE.
- 6) INSTALL SEDIMENT CONTROL STRUCTURE (SEDIMENT BASIN) TO SERVE AS SOUTH OUTFLOW EROSION CONTROL MANAGEMENT STRUCTURE. SEE DETAIL X ON SHEET C12 FOR MORE INFORMATION.

WORK AREA 2 (COMPLETE SITE) - STORM SEWER INSTALLATION

- 1) INSTALL NEW STORM SEWER AND DRAINAGE STRUCTURES THROUGHOUT PROJECT SITE, BEGINNING AT OUTFALL LOCATIONS.
- 2) INSTALL FLOOD LOGS IN MANHOLES S-1C2 AND S-1C2 AS SHOWN IN DETAIL ON SHEET C11.
- 3) AS NEW STORM SEWERS AND DRAINAGE STRUCTURES ARE INSTALLED THROUGHOUT GOLF COURSE, INSTALL FILTER BARRIERS, DOOR LOGS AND HYDROSEED / BLANKET OVER ALL UTILITY TRENCHES.

WORK AREA 3 (SOUTH) - WATERSHED G3 (7.30 ACRES OF DISTURBED AREA)

- 1) GRADE WORK AREA PER PLAN.
- 2) INSTALL TEMPORARY EROSION CONTROL, RISERS AT DRAINAGE STRUCTURES WITHIN WORK AREA AFTER COMPLETION OF FINAL GRADING.
- 3) INSTALL EROSION CONTROL, FABRIC OVER FINAL GRADING.
- 4) CLEAN NORTH EROSION CONTROL MANAGEMENT STRUCTURE OF SEDIMENT AT CONCLUSION OF WORK IN AREA.

WORK AREA 3 (SOUTH) - WATERSHED P1 & P2 (8.83 ACRES OF DISTURBED AREA)

- 1) GRADE WORK AREA PER PLAN.
- 2) INSTALL TEMPORARY EROSION CONTROL, RISERS AT OUTFALL STRUCTURES WITHIN WORK AREA AFTER COMPLETION OF FINAL GRADING.
- 3) INSTALL EROSION CONTROL, FABRIC OVER FINAL GRADING.
- 4) CLEAN SOUTH EROSION CONTROL MANAGEMENT STRUCTURE OF SEDIMENT AT CONCLUSION OF WORK IN AREA.

WORK AREA 4 (NORTH) - WATERSHEDS D1, D2, & K (19.29 ACRES OF DISTURBED AREA)

- 1) GRADE WORK AREA PER PLAN.
- 2) INSTALL TEMPORARY EROSION CONTROL, RISERS AT DRAINAGE STRUCTURES WITHIN WORK AREA AFTER COMPLETION OF FINAL GRADING.
- 3) INSTALL EROSION CONTROL, FABRIC OVER FINAL GRADING.
- 4) CLEAN NORTH EROSION CONTROL MANAGEMENT STRUCTURE OF SEDIMENT AT CONCLUSION OF WORK IN AREA.

WORK AREA 4 (SOUTH) - WATERSHED C (17.38 ACRES OF DISTURBED AREA)

- 1) GRADE WORK AREA PER PLAN.
- 2) INSTALL TEMPORARY EROSION CONTROL, RISERS AT DRAINAGE STRUCTURES WITHIN WORK AREA AFTER COMPLETION OF FINAL GRADING.
- 3) INSTALL EROSION CONTROL, FABRIC OVER FINAL GRADING.
- 4) CLEAN SOUTH EROSION CONTROL MANAGEMENT STRUCTURE OF SEDIMENT AT CONCLUSION OF WORK IN AREA.

WORK AREA 5 (NORTH) - WATERSHEDS M1, L1 & L2 (17.67 ACRES OF DISTURBED AREA)

- 1) GRADE WORK AREA PER PLAN.
- 2) INSTALL TEMPORARY EROSION CONTROL, RISERS AT DRAINAGE STRUCTURES WITHIN WORK AREA AFTER COMPLETION OF FINAL GRADING.
- 3) INSTALL EROSION CONTROL, FABRIC OVER FINAL GRADING.
- 4) CLEAN NORTH EROSION CONTROL MANAGEMENT STRUCTURE OF SEDIMENT AT CONCLUSION OF WORK IN AREA.

WORK AREA 5 (SOUTH) - WATERSHED D (10.72 ACRES OF DISTURBED AREA)

- 1) GRADE WORK AREA PER PLAN.
- 2) INSTALL TEMPORARY EROSION CONTROL, RISERS AT DRAINAGE STRUCTURES WITHIN WORK AREA AFTER COMPLETION OF FINAL GRADING.
- 3) INSTALL EROSION CONTROL, FABRIC OVER FINAL GRADING.
- 4) CLEAN SOUTH EROSION CONTROL MANAGEMENT STRUCTURE OF SEDIMENT AT CONCLUSION OF WORK IN AREA.

WORK AREA 6 (SOUTH) - WATERSHEDS A, B & C (11.58 ACRES OF DISTURBED AREA)

- 1) GRADE WORK AREA PER PLAN.
- 2) INSTALL TEMPORARY EROSION CONTROL, RISERS AT DRAINAGE STRUCTURES WITHIN WORK AREA AFTER COMPLETION OF FINAL GRADING.
- 3) INSTALL EROSION CONTROL, FABRIC OVER FINAL GRADING.
- 4) CLEAN SOUTH EROSION CONTROL MANAGEMENT STRUCTURE OF SEDIMENT AT CONCLUSION OF WORK IN AREA.

WORK AREA 7 (SOUTH) - WATERSHEDS F & G (10.47 ACRES OF DISTURBED AREA)


- 1) GRADE WORK AREA PER PLAN.
- 2) INSTALL TEMPORARY EROSION CONTROL, RISERS AT DRAINAGE STRUCTURES WITHIN WORK AREA AFTER COMPLETION OF FINAL GRADING.
- 3) INSTALL EROSION CONTROL, FABRIC OVER FINAL GRADING.
- 4) CLEAN SOUTH EROSION CONTROL MANAGEMENT STRUCTURE OF SEDIMENT AT CONCLUSION OF WORK IN AREA.



WORK AREA 8 (SOUTH) - WATERSHEDS H & I (8.46 ACRES OF DISTURBED AREA)

- 1) GRADE WORK AREA PER PLAN.
- 2) INSTALL TEMPORARY EROSION CONTROL, RISERS AT DRAINAGE STRUCTURES WITHIN WORK AREA AFTER COMPLETION OF FINAL GRADING.
- 3) INSTALL EROSION CONTROL, FABRIC OVER FINAL GRADING.
- 4) CLEAN SOUTH EROSION CONTROL MANAGEMENT STRUCTURE OF SEDIMENT AT CONCLUSION OF WORK IN AREA.

WORK AREA 8 (COMPLETE SITE) - FINAL EROSION CONTROL MANAGEMENT TASKS

- 1) REMOVE EROSION CONTROL STRUCTURE AT NORTHWEST CORNER OF WORK AREA G3 WHEN SITE IS FULLY STABILIZED. INSTALL FINAL STORM SEWER TO OUTFALL LOCATION.
- 2) REMOVE CONSTRUCTION ENTRANCE AT SHERMAN ROAD ENTRANCE.
- 3) REMOVE ALL SILT FENCE AROUND SITE PERIMETER AFTER SITE IS FULLY STABILIZED.





NOTES:


1. THESE CHANNELS SHALL BE CONSTRUCTED COINCIDING WITH STORM SEWER INSTALLATION, EACH INSTALLED IN AN OVER EXCAVATION 6\" BELOW POSITIVE DRAINAGE.
2. INSTALL TWO 4'X10' JUTE YARN MATT SPRAYED WITH POLYACRYLAMIDE (PAM) AS RECOMMENDED BY THE SUPPLIER.
3. REPLACE CHANEL LINING AS RECOMMENDED BY THE SOIL EROSION AND SEDIMENT CONTROL INSPECTOR.

SEDIMENT CONTROL STRUCTURE

Project Sequence:

Over-Excavation

Jute-Yarn Mat with PolyAcrylaMide (PAM)



Takeaways

- **Treatment Trains – Sequence of Sediment Controls**
- **SESC Design is an Iterative Process**
- **Visit the project site !**