

XX002007 AGGREGATE BICYCLE PATH (LCDOT)

Use this pay item on LCDOT Aggregate Bike Path projects where the aggregate material is Limestone Screenings. Delete this note from the Contract Specifications.

Effective: May 13, 2022

Description: This work shall consist of furnishing and placing two courses of aggregate totaling 6", on a prepared subgrade for bicycle path construction.

Materials: The materials shall meet the requirements of Article 402.02 of the "Standard Specifications" and the following:

The material shall be limited to limestone screenings, gradation FA 5, meeting the requirements of Article 1003.04 of the "Standard Specifications". Additionally, any material deemed incompatible according to Article 1003.01 (d) of the "Standard Specifications" will be rejected.

General: The work shall be performed according to Section 402 of the "Standard Specifications" and the following:

The aggregate surface course shall be constructed according to Articles 351.05(a) and 351.05(b) except that the bearing ratio requirements and the use of a central mixing plant to add moisture will be waived.

The aggregate shall be placed in 2 lifts with a total depth of 6". Water may be added at the job site to obtain density. The aggregate shall be compacted to not less than 95% of the standard density. The equipment pushing the spreader shall be non-cleated.

Method of Measurement: Aggregate Bicycle Path will be measured for payment in square yards according to Article 311.08(b) of the "Standard Specifications".

Basis of Payment: This work will be paid for at the contract unit price per square yard for AGGREGATE BICYCLE PATH. *The unit price shall include all material, equipment and labor required to furnish, transport, place and finish the construction of the aggregate bicycle path to the satisfaction and approval of the Engineer.*