

X0326XXX CENTERLINE – RUMBLE STRIP – X” (LCDOT)

Copy the Order of Operations below to the plan sheet(s) containing the pavement marking plan. The order may be revised by deleting bullets that don't apply e.g. delete the 3rd bullet if there aren't any recessed pavement markers on the project. Check with Traffic to confirm that Spray Thermoplastic will be used for the centerline or if another pavement marking material will be used. Delete this note from the special provision.

Effective: November 5, 2021

Revised: May 3, 2022

Description: This work shall consist of constructing rumble strips in the centerline of the pavement.

General: The centerline rumble strips shall be constructed according to Section 642 of the “Standard Specifications”, IDOT standard BD55 and/or as directed by the Engineer and the following:

Pavement Marking Order of Operations:

- The centerline pavement markings will be laid out.
- All survey monuments to be installed and or remain in place shall be located.
- Recessed Pavement Markers will be installed.
- The Centerline Rumble Strip will be constructed.
- At centerline survey monuments a 10' gap (5' either side of the monument) in the rumble strip shall be provided.
- The Spray Thermoplastic centerline markings will be placed.

Basis of Payment: This work will be paid for at the contract unit price per foot for CENTERLINE – RUMBLE STRIP of the width specified. *The unit price shall include all equipment, materials and labor required to construct the rumble strips.*